

CONSTRUCTION STANDARDS
SECTION CS 14
MARKERS AND DELINEATORS

CS 14-01 GENERAL: Markers and Delineators shall be furnished and installed at the locations shown on the Project Plans shall be in conformance with CALTRANS Standard Plans and Standard Specifications Section 82, Marker and Delineators except as modified by Section CS 14 of the City Standard Specifications and the Standard Drawings.

- A. All materials shall be furnished by the Contractor.
- B. Where flexible posts are shown on the Project Plans the posts shall be made from a flexible white plastic which shall be resistant to impact, ultraviolet light, ozone and hydrocarbons. Flexible posts shall resist stiffening with age and shall be free of burns, discoloration, contamination, and other objectionable marks or defects which affect appearance or serviceability.
- C. Each marker shall have a reflector consisting of a 3" x 18" (minimum) strip of silver reflective sheeting.

CS 14-02 PREPARATION

- A. The Contractor shall notify the Inspector a minimum of 48 hours prior to the day of layout of the proposed installation of Markers and Delineators.
- B. The Contractor shall be responsible for layout of all proposed installation of Markers and Delineators. The City must approve the layout of the proposed installation of Markers and Delineators.

CS 14-03 INSTALLATION: Unless otherwise shown on the Project Plans, the length of posts shall be 4 feet above the ground with two feet in the ground.